

M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

ABSTRACT OF COST FOR FURNITURE AND PANELLING WORK ALONG WITH BLINDS IN RECEPTION AREA AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no -

Date -

RECEPTION AREA = 25' X 35'6"					
RECEPTION SEATING					
RECEPTION TABLE -18' X 2'6" X 3'					
WALL PANELLING (12' X12')					
1		Providing and fixing 25 mm thick shutters for cupboards etc.including black enamelled M.S. butt hinges with necessary screws : Panelled or panelled and glazed shutters	20.0		sqm
2		Providing and fixing Pre-laminated medium density fibre board IS: 14587:1998 marked, with one side decorative lamination other side balancing lamination Grade-I(exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 2.00 mm thick of approved brand (fittings to be paid separately). Pre-laminated with decorative lamination one side and other side balancing lamination exterior Grade - I MDF Board 18 mm thick confirming to IS:14587	20.0		sqm
3		SCREW , BOLTS AND ADHESIVE		LS	
LIGHT AND LOGO					
4		Diffused light of approximate length (desired colour and brand)	10.0		m
5		fixtures like switch board and other miscellaneous charges		lumsum	
6		metallic name plate (3" high letters) (DAV Public school, sheikhpora)	75.0		inch
7		school LOGO (1' dia marquee glow board)		lumsum	
SOFA SETS AND BLINDS					
8		Ready made 2 seater sofa of renound companies like Juari	6.0		each
9		BLINDS over windows	98.0		sqft
			TOTAL COST		

SAY TOTAL -

NOTE:

Rates are inclusive of G.S.T.

M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

ABSTRACT OF COST FOR PAINTING OF RECEPTION AREA AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no -

Date -

RECEPTION AREA = 25' X 35'6"						
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
INTERIOR PAINTING AND FINISH (INCLUDING WALL, CEILING AND BEAMS)						
1		Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete	260		sqm	
2		Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	260		sqm	
3		Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm.	260		SqM	
ENAMEL PAINTING						
4		Applying priming coat with ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works.	36		34.60	
5		Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	36		54.30	
TOTAL COST						

SAY TOTAL - ONLY

..... ONLY

NOTE:

Rates are inclusive of G.S.T.

M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

ABSTRACT OF COST FOR FALSE CEILING OF RECEPTION AREA AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no -

Date -

RECEPTION AREA = 25' X 35'6"						
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		FALSE CEILING	888.0		SQFT	
1		Providing and fixing at all height false ceiling of 12.5 mm thick -tapered edge gypsum board conforming to IS : 2095 including - providing and fixing as per specification and mention in SOR.	82.5		Sq m	
2		LED AT LIGHT POINTS (UNIT WISE) (inclusive of wire and wiring)	30.0		each	
3		Diffused light of approximate length (desired colour and brand)	45.0		m	
4		Electrical work and fittings per light	30.0		each	
5		fixtures like switch board and other miscellaneous charges			lumsun	
			TOTAL COST			

SAY TOTAL - ONLY

..... ONLY

NOTE:

Rates are inclusive of G.S.T.

M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

ABSTRACT OF COST FOR ALUMINUM WORK IN RECEPTION AREA AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no -

Date-.....

RECEPTION AREA = 25' X 35'6"						
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
ALUMINUM DOOR (3 DOORS 11'6" X 8')						
1		Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge Pre-laminated particle board with decorative lamination on both sides	25.6		Sq m	
2		Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness(weight not less than 12.50 kg/sqm)	25.6		sqm	
3		Miscellaneous items and other fitting and fixture charge		L.S		
				TOTAL COST		

SAY TOTAL - ONLY

..... ONLY

NOTE:

Rates are inclusive of G.S.T.

M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

ABSTRACT OF COST FOR AIR CONDITIONING OF RECEPTION AREA AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no -

Date -

RECEPTION AREA = 25' X 35'6"						
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
AIRCONDITIONING						
1		providing 2 tonne AC of reputed brands along with stabilisers	3.0		Sq m	
2		installation, pipe layout and connection	3.0		sqm	
TOTAL COST						

SAY TOTAL - ONLY

..... ONLY

NOTE:

Rates are inclusive of G.S.T.