

# M/S HAPPY AND ASSOCIATES

ARCHITECTS , ENGINEERS , INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociate@gmail.com, sinha.prashant100@gmail.com

## ABSTRACT OF COST FOR SOIL FILLING AND PAVER LAYING ON GROUND AT -DAV PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no - DAV-HA-.....

Date - .....

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		<b>AREA OF SOIL FILLING</b>	<b>43,668</b>		<b>SQFT</b>	
		<b>AVERAGE DEPTH OF FILLING</b>	<b>4.0</b>		<b>FT</b>	
1		Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.				
		total soil filling and leveling (after levelling and ramming to finished be at 2'6')	4951.0		Cu m	
		<b>PAVER</b>	<b>3,250</b>		<b>SQFT</b>	
2		Providing and laying factory made chamfered edge Cement Concrete paver blocks of required strength,thickness & size/shape, made by table vibratory method , to attain superior smooth finish using PU or equivalent moulds, laid in required Grey colour & pattern over 50mm thick compacted bed of coarse sand, compacting and proper embedding / laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks,lawns, drive ways or light traffic parking etc. all complete as per manufacturer's specifications & direction of Engineer -in-Charge: (a) 80 mm thick c.c. paver block of M-35 grade with approved colour design and pattern.	302.0		SQM	
			<b>Total</b>			
<b>SAY TOTAL COST - Rs .....</b>						
.....						

Note :

Rates are inclusive of G.S.T.

As per contour drawing, soil filling suggested to be levelled at 4' because filling more than this would lead to boundary height issues