



DAV PUBLIC SCHOOL

Chakandra More, Chewara Road, Sheikhpura - 811304 (Bihar)

An English Medium Co-Educational School

(Affiliated to CBSE New Delhi upto Secondary Level, Affiliation No. 331071, School Code No. 66810)

E-mail : davsheikhpura@gmail.com | website : www.davpsheikhpura.com

Ref No. DAV/SHEIKHPURA/2026/91

Date : 07/07/2026

TENDER NOTICE

SEALED QUOTATIONS ALONGWITH FINANCIAL BID AND TECHNICAL BID ARE INVITED FOR **CONSTRUCTION OF WATER TANK** ON MUMTY / HEAD ROOM AT DAV PUBLIC SCHOOL, SHEIKHPURA TO BE SUBMITTED AT SCHOOL COUNTER LATEST BY **17th JULY 2026** (03:00 PM). BOQ & DESIGN ARE ALSO ATTACHED HEREWITH.

Note: Contractor have to visit the site before filling the bid.

(Sudha Jha)
Principal

(Mr. Niraj Kumar Singh)
Manager

(Mrs. Sabita)
A.R.O.

ABSTRACT OF COST FOR CONSTRUCTION OF WATER TANK ON MUMTY FOR NEW BLOCK AT D.A.V PUBLIC SCHOOL, SHEIKHPURA, BIHAR

Ref no

Date

S.NO	SOR	PARTICULARS	QUANTITY	RATE	UNIT	AMOUNT
		Cov Area (in sqft)			355.0	
		CAPACITY (in litres)			40000 approx	
1	na	site preparation			lumpsum	
2	5.2.3	Reinforced cement concrete work in wall (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. up to floor five level excluding cost of centring, shuttering, finishing and reinforcement. 1:2:4(1 cement :2 coarse sand:4 graded stone aggregate 20 mm nominal size)	9.9		cum	0
3	5.3	R C C work in beams,suspended floors, roofs having slope upto 15, landings,balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size).	10.5		Cu m	0
4	5.9	Centring and shuttering including strutting,propping etc. and removal of form for.				
	5.9.3	Suspended floors, roof, landings, balconies and access platform.	66.0		sq m	0
	5.9.6	Columns,Pillars, Piers, Abutments, Posts and Struts	25.0		sq m	0
5	5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
	5.22.7A	Thermo-Mechanically Treated bars TMTC-500-8mm dia.	1,080.0		KG	0
	5.22.7B	Thermo-Mechanically Treated bars TMTC-500-10mm dia.	1,240.0		KG	0
	5.22.7C	Thermo-Mechanically Treated bars TMTC-500-12mm dia.	1,320.0		KG	0
	5.22.7D	Thermo-Mechanically Treated bars TMT Fe-500-16mm dia.	1,560.0		KG	0

6	6.1.14A	Brick work with bricks of class designation 100A in foundations and plinth in :Cement mortar 1:6 (1 cement: 6 coarse sand)				
	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum				
			4.3		Cu m	0
7	13.11.4	12 mm cement plaster of mix:1:6 (1 cement: 6 coarse sand)	36.0		sq m	0
8	13.24.2	6 mm cement plaster to ceiling of mix :1:4(1 cement: 4 coarse sand)	77.0		sq m	0
9	MR	Providing and applying ULTRA TECH URP waterproofing chemical with cement. 1st coat in ratio of 1:2, 2nd coat in ratio of 1:3 and finishing with final coat of ULTRA TECH : Also conducting 8 days complete water test	77.0		sqm	0
10	13.77.2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shadeNew work (two or more coats) over and including priming coat with cement primer	77.0		Sq m	0
11	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (Thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy , bottle green , black of any size as approved by Engineer-in-charge in skirting , risers of steps and dados over 12 mm thick bed of cement Motar 1:3(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	77.0		Sq m	0
12	MR	Brass full way valve with C.I. wheel (screwed end) 25 mm dia	2.0		each	0
13	18.3.3	Providing and fixing Polyethelene-Aluminium-Polyethelene (PE-ALPE) Composite Pressure Pipes conforming to IS - 15450, including all special fittings of composite materials 2025 (25 mm OD) pipe	30.0		metre	0
14	MR	Metal access ladder (grouted to the wall for accessing the tanks)	2.7		metre	0
TOTAL						0

SAY TOTAL =ONLY
IN WORDS.....

Note:
Rate inclusive of GST
Carriage cost not included in the estimate as per instruction of DAV CMC, Delhi